



ERECTION NOTES

1. HEART INDICATES MARKED END OF MEMBER. MEMBERS TO BE ERECTED WITH ASSEMBLY MARK AT THIS LOCATION.
2. COLUMNS HAVE ASSEMBLY MARK STAMPED ON SOUTH OR EAST FACING FLANGE NEAR BASE OF SHAFT UNO.
3. VERTICAL BRACING, STAIRS, HANGERS, AND OTHER INCLINED MEMBERS HAVE ASSEMBLY MARK STAMPED ON TOP END. MARKS WITH ASTERISK ARE STAMPED ON BOTTOM END.
4. FIN PLATES FOR CHANNELS ARE ON HEEL UNLESS SHOWN OTHERWISE.
5. FIN PLATES FOR BEAMS WILL BE ON NORTH OR WEST SIDE OF BEAM WEEL UNLESS SHOWN OTHERWISE. IN ERECT BEAMS TO SOUTH OR EAST SIDE OF CLEAT.

ERECTION PLAN REFERENCE:

No.	DATE	DETAILS

Xtech Drafting Pty. Ltd.
 A.B.N. 30 105 598 865
 14 / 37 - 39 ALBERT RD. MELBOURNE VIC AUSTRALIA 3004
 PH: +61 3 9566 1015 FAX: +61 3 9566 1016 MOB: 0411 966 695

GREENSBOROUGH STEEL FAB.
 15 DENNIS ST. CAMPBELLFIELD 3061 PH 9305 1677 FAX 9305 2117

BAULDERSTONE HORNIBROOK THE ALFRED CENTRE - STAGE 2		ISOMETRIC	
DRAWN: AM	CHECKED: AM	DRAWING No.	REV.
DATE: 07.04.2009	SCALE: 1/100	203-MP-01	