



ERECTION NOTES

1. INDICATES MARKED END OF MEMBER. MEMBERS TO BE ERECTED WITH ASSEMBLY MARK AT THIS LOCATION.
2. COLLUMS HAVE ASSEMBLY MARK STAMPED ON NORTH OR EAST FACING FLANGE NEAR BASE OF SHAFT UNLESS OTHERWISE SHOWN.
3. VERTICAL BRACING, STAIRS, HANGERS, AND OTHER INCLINED MEMBERS HAVE ASSEMBLY MARK STAMPED ON TOP END MARKS WITH ASTERISK ARE STAMPED ON BOTTOM END.
4. FIN PLATES FOR CHANNELS ARE ON HEEL UNLESS SHOWN OTHERWISE.

5. FIN PLATES FOR BEAMS WILL BE ON NORTH OR WEST SIDE OF BEAM WEB, UNLESS SHOWN OTHERWISE, IF ERECT BEAMS TO SOUTH OR EAST SIDE OF CLEAT.

ERECTION PLAN REFERENCE:

No	REV	DESCRIPTION	DATE

Xtech Drafting Pty. Ltd.

A.B.N. 49 079 793 122
 14/37 - 39 ALBERT RD MELBOURNE VIC AUSTRALIA 3004
 PH: +61 3 9866 1015 FAX: +61 3 9077 0101

WESTYS FABRICATIONS PTY. LTD.

909-913 Burwood Hwy, Ferntree Gully, Vic. 3156 Ph: 03 97583166

DESIGN ENGINEER:

BLUE CROSS AGED CARE DEVELOPMENT
39 LIVINGSTONE RD. VERMONT SOUTH
ISOMETRIC

DRAWN:	CHECKED:	DRAWING No:	REV:
AWM	AWM	BCC-MP-01	
DATE:	SCALE:		
	1:100		

T:\file\10000000